



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2010 Chevrolet Camaro

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- A failure to crank.
- Longer than normal cranking cycle times.
- Slow, hard cranking.
- Various electrical component failures up to and including a dead battery.

The technician may find low battery codes stored in the system, but not in all cases.

Cause: A possible cause for the above conditions is a poor connection to the under-hood battery cable junction block, located near the left front strut tower.

Correction: Follow the manufacturer's recommended diagnostic and repair procedures which include inspecting, cleaning the terminals and properly tightening the fastener.