



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2010 Buick Lucerne 3.9L

Conditions: The operator of the vehicle may complain that the vehicle will crank but not start when the key is turned to the crank (start) position.

Cause: A potential cause for the above condition is a poor connection to the rear fuse block located under the rear seat. The poor connection prevents power from being supplied to the fuel pump.

Correction: Inspect and repair the above condition following the manufacturer's recommended diagnostic and repair procedures.