



TECH TIPS

Dixie Part Numbers: S-1422, S-1491, S-1497, S-1498, S-1499, S-1502

Applications:

- 2005 - 2006 Buick Rendezvous 3.5L
- 2005 - 2006 Buick Terra 3.5L
- 2006 Chevrolet Impala 3.5L, 3.9L(including flex fuel)
- 2004 – 2006 Chevrolet Malibu 3.5L
- 2004 – 2006 Chevrolet Malibu Max 3.5 L
- 2006 Chevrolet Monte Carlo 3.5L, 3.9L(including flex fuel)
- 2006 Chevrolet Uplander 3.5L, 3.9L
- 2006 Pontiac G6 3.5L, 3.9L
- 2006 Pontiac Montana SV6 3.5L, 3.9L
- 2006 Saturn Relay-2 3.5L
- 2006 Saturn Relay-3 3.5L, 3.9L

Condition: Some vehicle operators may complain of one or more of the following conditions:

- That intermittently the starter has an extended crank time when the engine is hot.
- That the starter may not disengage after the engine starts.

Cause: A possible cause for the above conditions is an out-of-date calibration file in the powertrain control module.

Correction: Follow the manufacturer's recommended procedures for diagnosing that the condition is caused by the out-of-date calibration file and only then update the calibration file following the manufacturer's recommended procedures.

Revision 20090716: Expanded vehicle range

REV: 20090716

Courtesy of APRA

TSB_125.doc

Dixie *Tech Tips* are intended for use by professional technicians, and are not for the general public. They are written to inform technicians of conditions that may exist or as a guide to aid in diagnosing and servicing a vehicle. All references to original equipment manufactures, vehicle manufactures and any other Trade Mark names are for the sole purpose of identifying the vehicle and or part that the *Tech Tip* applies to. This document is property of Dixie Electric Ltd. and is not to be copied or distributed with out written permission.