



TECH TIPS

Dixie Part Numbers: S-1519

Applications: 2007 Jeep Wrangler 3.8L

Condition: The operator of vehicle may complain of one or more of the following vehicle conditions:

- Extended cranking cycle
- Multiple crank cycles prior to the engine starting

Cause: A potential cause for the above conditions is an incorrectly positioned camshaft sensor resulting in the camshaft sensor being too close and/or coming in contact with the camshaft gear

Correction: Follow the manufacturer's recommended procedures to check and/or replace the cam shaft sensor.