



TECH TIPS

Dixie Part Numbers: A-1705 A-1758 A-6548 A-80198
 A-80201 S-1468 S-1511 S-1515

Applications: 2006 – 2010 Cadillac DTS
 2007 – 2010 Cadillac Escalade with heated rear seats
 2007 – 2010 Cadillac Escalade ESV with heated rear seats
 2007 – 2010 Chevrolet Suburban with heated rear seats
 2007 – 2010 Chevrolet Tahoe with heated rear seats
 2007 – 2010 GMC Yukon with heated rear seats
 2007 – 2010 GMC Yukon XL with heated rear seats

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- No crank
- Slow crank
- No start
- Discharged or low battery

Cause: A potential cause for the above conditions is the rear heated seats module discharging the battery by keeping the data line active after the ignition has been shut off.

Correction: The manufacturer has released an updated calibration file for the rear heated seats module to correct the above situation.

REV:20101220 Added DTS application and associated unit numbers