



TECH TIPS

Dixie Part Numbers: A-2073 A-2078 A-2098 A-2105
 A-2112 A-80401

Applications: 2007 – 2008 Ford Expedition 5.4L
 2007 – 2008 Ford F-150 4.6L and 5.4L
 2007 – 2008 Ford Mustang 4.6L and 5.4L
 2007 – 2008 Lincoln Mark LT 5.4L
 2007 – 2008 Lincoln Navigator 5.4L
 2007 – 2008 Mercury Mountaineer 5.4L

Condition: The operator of the vehicle may complain of a high pitched metallic whistle when starting the engine below 5°C (after cold soak). The noise is most prevalent at idle speed for 10 minutes after start-up with the cold ambient temperatures.

Cause: A possible cause for this is a faulty idler pulley.

Correction: The manufacturer recommends replacing the idler pulley with a new one (dealer part number 6L3Z-6C348-A) following the manufacturer's recommended procedures.

REV:20100128 Updated Part Number Listing