



TECH TIPS

Dixie Part Numbers: A-469 A-470 A-472
 A-6374 A-6398

Applications: 1994 – 2001 Land Rover Range Rover
 1998 – 2001 Land Rover Discovery II

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The belt chirping under load
- The belt slipping
- The belt requiring frequent replacement.

Cause: A potential cause for the above conditions is a faulty idler pulley that may cause the belt to wear and slip prematurely.

Correction: Inspect under the hood of the vehicle to see if there is a decal referring to service campaign H369, if so then the faulty idler pulley has already been replaced, if not, follow the manufacturer's recommended replacement procedures.