



TECH TIPS

Dixie Part Numbers: S-6222

Applications: 1998 – 2000 Rodeo and Amigo 2.2L applications

Condition: Some vehicle operators may complain of prolonged cranking when restarting the engine when cold.

Cause: The Powertrain Control Module is programmed with a feature to prevent engine flooding at cold temperatures when the engine fails to start. The feature disables the fuel injection from 5 to 8 seconds if the engine fails to start while cranking in cold temperatures.

Correction: The manufacturer does not show any repair for this condition, it is for information purposes only.