



TECH TIPS

Dixie Part Numbers: S-6255

Applications: 2004 Audi RS6

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The engine cranks slowly.
- The engine intermittently does not crank.

The technician may observe a high voltage drop in the negative portion of the circuit.

Cause: A potential cause for the above condition is a loose or corroded ground-strap connection at either the engine block or right side rail location.

Correction: Follow the manufacturer's recommended procedures to inspect and correct the ground connection which includes replacing the nut with the a new one, manufacturer's number 1J0 971 254 A.