



TECH TIPS

Dixie Part Numbers: Not Applicable

Applications: 2007 – 2008 Ducati 1098
2007 – 2008 Ducati 1098 Tricolore
2007 – 2008 Ducati 1098S
2008 – 2009 Ducati 1098R
2008 – 2009 Ducati 848

Condition: The operator of the vehicle may complain of erratic charging up to and including failure of the charging system.

Cause: A potential cause for the above condition is the rectifier/regulator module located below the seat. The manufacture has identified that excessive heat from the exhaust may have a negative affect on the rectifier/regulator module.

Correction: The manufacturer suggests replacing the regulator, installing a heat guard between the regulator and exhaust system and a modified battery support.