



TECH TIPS

Dixie Part Numbers: S-6045 S-6087

Applications: 1968 – 1980 Saab All Applications

Condition: The operator of the vehicle may complain that the engine cranks slowly, is hard to start and/or fails to turn over.

Cause: A potential cause for the above conditions is a high voltage drop in the vehicle ignition wire to the starter. The solenoid requires a minimum of 9.0V to energize.

Correction: The manufacturer has a repair kit to rectify the problem (Saab part number 191-911-251).