



TECH TIPS

Dixie Part Numbers: S-6246 S-6258 S-6273 S-6565

Applications: 2006 – 2008 BMW 3 Series
2006 – 2008 BMW X5
2007 – 2008 BMW 5 Series
2007 – 2008 BMW 6 Series
2008 BMW 1 Series
2008 BMW X6

Condition: The technician may note that the vehicle fails to cranks after replacing the Car Access System.

Cause: A possible cause for the above is that the Car Access System *Line mode* is still active.

Correction: The ISTA (the online service system for BMW and Mini) must be used to update the Line mode. Follow the manufacturer's recommended procedures **take care as the procedure differs for each model.**