



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2011 Dodge Journey (MDH1122xx to MDH0221) without the Tip Start Option Installed (option code XBN)

Condition: The operator of the vehicle may complain that the engine cranks but will not start.

Cause: The factory installed vehicle starting logic had the cranking cycle time limited to 2 seconds.

Correction: Follow the manufacturers recommended diagnostic and repair reconfiguration procedures, which include installing the Tip Start logic, which has a 10 second cranking cycle time, when applicable.