



TECH TIPS

Dixie Part Numbers: S-80372 S-80373 TBA

Applications: 2008 – 2009 Mitsubishi Lancer M/T built prior to 02/26/2008
2008 – 2009 Mitsubishi Lancer A/T built prior to 02/22/2008

Condition: The operator of the vehicle may complain that the vehicle has an extended crank time or fails to start while cranking. The engine may start if the accelerator pedal is pressed down slightly.

Cause: A potential cause for the above conditions is a flaw in the engine control module software that does not open the electronic throttle valve adequately, preventing sufficient airflow.

Correction: Follow the manufacturer's recommended repair procedures to diagnose and update the engine control module software if applicable.

