



TECH TIPS

Dixie Part Numbers: A-80018 A-80375

Applications: 2006 – 2007 Mitsubishi Raider 3.7L

Condition: The operator of the vehicle may complain of a chirping sound when the steering wheel is turned to a full lock position.

Cause: A potential cause for the above conditions is a slipping alternator belt.

Correction: On applications where the above is a concern the manufacturer recommends replacing the factory supplied pulley with a clutch pulley. Follow the manufacturer's recommended replacement procedures when applicable which includes shimming the pulley out to the appropriate position.