



TECH TIPS

Dixie Part Numbers: S-8356

Applications: 1996 – 1997 Chrysler Town & Country
1996 – 1997 Dodge Caravan
1996 – 1997 Plymouth Voyager

Condition: The operator of the vehicle may experience that the starter partially disengages and then re-engages during the cranking cycle creating audible pinion noise.

Cause: A possible cause for the above is an incorrectly programmed Powertrain Control Module (PCM).

Correction: Follow the manufacturer's recommended procedures to ensure that the most current calibration file is loaded in the PCM prior to performing any other diagnostics for the above condition.

REV:20101220 Changed S-8343 to S-8356

REV: 20101220

Courtesy of Dixie Archives

TSB_861.doc

Dixie *Tech Tips* are intended for use by professional technicians, and are not for the general public. They are written to inform technicians of conditions that may exist or as a guide to aid in diagnosing and servicing a vehicle. All references to original equipment manufactures, vehicle manufactures and any other Trade Mark names are for the sole purpose of identifying the vehicle and or part that the *Tech Tip* applies to. This document is property of Dixie Electric Ltd. and is not to be copied or distributed with out written permission.