



TECH TIPS

Dixie Part Numbers: A-9517 A-9518

Applications: 2007 Opel GT (Export) 2.0L Turbo – VIN X up to VIN 7Y113626
2007 Pontiac Solstice 2.0L Turbo – VIN X up to VIN 7Y113626
2007 Saturn Sky Redline 2.0L Turbo – VIN X up to VIN 7Y113626

Condition: The operator of the vehicle may complain that when driving the vehicle at slow speeds with high electrical loads, the charge warning light flickers.

Cause: A possible cause is that the alternator can not meet the demands of the system at low speed. The technician may find that diagnostic trouble code P0626 stored in the system.

Correction: Perform a standard test of the electrical system and if no problems are observed the calibration file for the electronic control module will require updating. Follow the manufacturer's recommended procedures for updating the calibration file.